



## CRT LABORATORIES, INC.

1680 North Main Street, Orange, CA 92867

Tel.: (714) 283-2032

www.crtlabs.com • e-mail: ctrlabs@ctrlabs.com

ASTM Physical & Mechanical • Chemical-Thermal Analysis • IAPMO Cell Class  
Geosynthetic Materials • Plumbing & Faucet Assemblies • Resin & Finished Product Testing



## TEST REPORT

PAGE 1 OF 4

FOR: Reliance Worldwide Corporation  
14284 Danielson Street  
Poway, CA 92064  
Tel: (760) 705-1235 / Fax: (760) N/A  
ATTN: Ryan Miller

LWR NO.: 21219 DATE: Oct. 15, 2020

### BACKGROUND:

The client submitted three (3) samples for testing. The samples arrived on 09/29/2020 via customer delivery. Visual inspection was performed on 09/29/2020 and no product defects were noted. All samples submitted for load testing in accordance with WW-H-171-E ANSI/MSS SP-58. Testing in accordance with customer instructions, P.O. No. 4500129066, and signed CRT quotation dated 09/30/2020. The following additional information is provided:

**CRT order entry log date:** 09/30/2020 / **Report due date:** 10/16/2020

### PRODUCT ID:

Three (3) samples of Water Dam Test Configurations, identified as;

- 1) INJ-WP-HFEXT81/
- 2) INJ-WP-HFEXT101
- 3) INJ-WP-HFEXT121

### ASSIGNED TESTING:

Set-up & perform testing in accordance with client test objective & requirements provided (WW-H-171-E ANSI/MSS SP-58)

### TEST METHOD:

**WW-H-171-E ANSI/MSS SP-58**

**Load Test @ 23°C** – 4 specimens to be tested. Maximum load to be reached in ≤ 1 minute

### TEST RESULTS:

The results of testing are reported on tables 1-3, attached.

### CONCLUSION:

The above samples comply with WW-H-171-E ANSI/MSS SP-58 Load Test...*Complies.*

Specimen Retain Bin: BB (Samples were discarded after testing per client instructions)

Signed on behalf of;

## CRT LABORATORIES, INC.

IAPMO R&T



ISO 9001:15 Certified – Registered / ISO/IEC 17025:05 Recognized Co.

Ken A. Le Jeune  
CEO / Laboratory Director

Raul Gonzalez  
Laboratory Technician





# CRT LABORATORIES, INC.

1680 North Main Street, Orange, CA 92867

Tel.: (714) 283-2032

www.crtlabs.com • e-mail: crtllabs@crtlabs.com

ASTM Physical & Mechanical • Chemical-Thermal Analysis • IAPMO Cell Class  
Geosynthetic Materials • Plumbing & Faucet Assemblies • Resin & Finished Product Testing



## TEST REPORT

PAGE 2 OF 4

FOR: Reliance Worldwide Corporation  
14284 Danielson Street  
Poway, CA 92064  
Tel: (760) 705-1235 / Fax: (760) N/A  
ATTN: Ryan Miller

LWR NO.: 21219 DATE: Oct. 15, 2020

### TABLE 1

SCOPE: Load testing @ 73°F

SAMPLE ID: Water Dam Test Configurations, INJ-WP-HFEXT81/

TEST SAMPLE	APPLIED LOAD (LBS)	TIME TO REACH APPLIED LOAD (S)	TEST RESULT (PASS/FAIL)
8-1	1,351	32	Pass. No failure, damage or deformation
8-2	1,353	32	Pass. No failure, damage or deformation
8-3	1,351	31	Pass. No failure, damage or deformation
8-4	1,352	32	Pass. No failure, damage or deformation

REQUIREMENTS: Load test @ 73°F (1260lb + 126lb). Maximum load to be reached in ≤ 1 minute

...Complies



Sample before loaded



Sample after loaded. No failure, damage or deformation





# CRT LABORATORIES, Inc.

1680 North Main Street, Orange, CA 92867

Tel.: (714) 283-2032

www.crtlabs.com • e-mail: crtllabs@crtlabs.com

ASTM Physical & Mechanical • Chemical-Thermal Analysis • IAPMO Cell Class  
Geosynthetic Materials • Plumbing & Faucet Assemblies • Resin & Finished Product Testing



## TEST REPORT

PAGE 3 OF 4

FOR: Reliance Worldwide Corporation  
14284 Danielson Street  
Poway, CA 92064  
Tel: (760) 705-1235 / Fax: (760) N/A  
ATTN: Ryan Miller

LWR NO.: 21219 DATE: Oct. 15, 2020

### TABLE 2


SCOPE: Load testing @ 73°F

SAMPLE ID: Water Dam Test Configurations, INJ-WP-HFEXT101

TEST SAMPLE	APPLIED LOAD (LBS)	TIME TO REACH APPLIED LOAD (S)	TEST RESULT (PASS/FAIL)
10-1	2,002	31	Pass. No failure, damage or deformation
10-2	2,003	32	Pass. No failure, damage or deformation
10-3	2,003	31	Pass. No failure, damage or deformation
10-4	2,002	31	Pass. No failure, damage or deformation

REQUIREMENTS: Load test @ 73°F (1912lb + 191lb). Maximum load to be reached in ≤ 1 minute

...Complies



Sample before loaded



Sample after loaded. No failure, damage or deformation





**CRT LABORATORIES, Inc.**

1680 North Main Street, Orange, CA 92867

Tel.: (714) 283-2032

www.crtlabs.com • e-mail: ctrlabs@crtlabs.com

ASTM Physical & Mechanical • Chemical-Thermal Analysis • IAPMO Cell Class  
Geosynthetic Materials • Plumbing & Faucet Assemblies • Resin & Finished Product Testing



## TEST REPORT

PAGE 4 OF 4

FOR: Reliance Worldwide Corporation  
14284 Danielson Street  
Poway, CA 92064  
Tel: (760) 705-1235 / Fax: (760) N/A  
ATTN: Ryan Miller

LWR NO.: 21219 DATE: Oct. 15, 2020

### TABLE 3


**SCOPE:** Load testing @ 73°F

**SAMPLE ID:** Water Dam Test Configurations, INJ-WP-HFEXT121

TEST SAMPLE	APPLIED LOAD (LBS)	TIME TO REACH APPLIED LOAD (S)	TEST RESULT (PASS/FAIL)
12-1	2,855	32	Pass. No failure, damage or deformation
12-2	2,850	31	Pass. No failure, damage or deformation
12-3	2,852	31	Pass. No failure, damage or deformation
12-4	2,857	32	Pass. No failure, damage or deformation

**REQUIREMENTS:** Load test @ 73°F (2652lb + 265lb). Maximum load to be reached in  $\leq 1$  minute

*...Complies*



Sample before loaded



Sample after loaded. No failure, damage or deformation